Family history and polygenic risk of cardiovascular disease: independent factors associated with secondary cardiovascular manifestations in patients undergoing carotid endarterectomy

Nathalie Timmerman[1], Dominique P.V. de Kleijn[1], Gert Jan de Borst[1], Hester M. den Ruijter[3], Folkert W. Asselbergs[4,5,6], Gerard Pasterkamp[2], Saskia Haitjema[2]*, Sander W. van der Laan[2]*.

Affiliations

1 Department of Vascular Surgery, Division of Surgical Specialties, University Medical Centre Utrecht, Utrecht University, Utrecht, the Netherlands;

2 Laboratory of Clinical Chemistry and Hematology, Division Laboratories and Pharmacy, University Medical Centre Utrecht, Utrecht University, Utrecht, the Netherlands;

3 Laboratory of Experimental Cardiology, Division Heart & Lungs, University Medical Centre Utrecht, Utrecht University, Utrecht, the Netherlands;

4 Department of Cardiology, Division Heart & Lungs, University Medical Centre Utrecht, Utrecht University, Utrecht, the Netherlands;

5 Durrer Center for Cardiogenetic Research, ICIN-Netherlands Heart Institute, Utrecht, the Netherlands;

6 Institute of Cardiovascular Science, Faculty of Population Health Sciences, University College London, London, UK.

* These authors jointly supervised this project.

Correspondence to:

Sander W. van der Laan, PhD, Laboratory of Clinical Chemistry and Hematology, Division Laboratories, Pharmacy and Biomedical Genetics; University Medical Centre Utrecht; Utrecht University; Heidelberglaan 100, 3584 CX Utrecht, The Netherlands; Phone: +31 (0)88 756 7696; E-mail: s.w.vanderlaan-2@umcutrecht.nl

Declarations of interest: none

Short title: Family history and polygenic risk are independently associated with sCVE

Category: Original article

3 tables, 3 figures (supplemental: 8 tables, 1 figure)

Word count abstract: 250

Total word count manuscript: 4998

Abstract

Word count: 250

Background

Family history (FHx) of cardiovascular disease (CVD) is a risk factor for CVD and a proxy for cardiovascular heritability. Genetic studies have identified dozens of variants for CVD underscoring its heritable component. CVD variants have also been associated with atherosclerotic plaque composition. However, little is known about the influence of FHx or genetic burden on secondary cardiovascular events (sCVE).

Methods

We included 1,788 carotid endarterectomy patients from the Athero-Express Biobank. A weighted polygenic risk score for CAD including 1.7 million variants was calculated (MetaGRS). The composite endpoint of sCVE during three years follow-up included coronary, cerebrovascular and peripheral events and cardiovascular death. We assessed the impact of FHx and MetaGRS on sCVE and carotid plaque composition.

Results

Positive FHx was associated with a higher 3-year risk of sCVE independent of cardiovascular risk factors and MetaGRS (adjusted HR 1.40, 95%CI 1.07-1.82, p=0.013). Patients in the highest MetaGRS quintile had a higher 3-year risk of sCVE compared to the rest of the cohort independent of cardiovascular risk factors including FHx (adjusted HR 1.35, 95%CI 1.01-1.79, p=0.043), and their atherosclerotic plaques contained more fat (adjusted OR 1.59, 95%CI, 1.11-2.29, p=0.013) and more macrophages (OR 1.49, 95%CI 1.12-1.99, p=0.006).

Conclusion

In patients with severe atherosclerotic disease, both positive FHx and higher MetaGRS were independently associated with increased risk of sCVE. Moreover, higher MetaGRS was associated with vulnerable plaque characteristics. Future studies should unravel underlying mechanisms and focus on the added value of polygenic scores and family history in individual risk prediction for sCVE.

Key words:

Atherosclerosis

Polygenic risk score

Family history

Vascular biology

Carotid artery stenosis

Carotid endarterectomy

Abbreviations

PRS	polygenic risk score
CVD	cardiovascular disease
CAD	coronary artery disease
SNP	single-nucleotide polymorphism
FHx	family history of premature CVD
MetaGRS	polygenic risk score for CAD including 1.7 million SNPs associated with CAD
CEA	carotid endarterectomy
CVE	cardiovascular event
sCVE	secondary cardiovascular event
MI	myocardial infarction
AAA	abdominal aortic aneurysm
ACS	acute coronary syndrome defined as a composite of myocardial infarction and unstable angina pectoris
PAD	peripheral artery disease
GWAS	large-scale genome wide association studies

Introduction

Family history of cardiovascular disease (FHx) is a major risk factor for primary cardiovascular disease (CVD) and serves as a surrogate for genetic predisposition.[1,2] Risk prediction for secondary cardiovascular events remains challenging as traditional risk factors have limited discriminative performance.[3] The main underlying mechanism of CVD is atherosclerosis, and atherosclerotic plaque composition, exemplified by intraplaque haemorrhage (IPH), was shown to be associated to adverse secondary cardiovascular events (sCVE).[4] Yet, the relevance of FHx for secondary outcome of cardiovascular events is still unclear. [5–9]

Large-scale genome-wide association studies (GWAS) have identified hundreds of common genetic variants (single-nucleotide polymorphisms or SNPs) robustly associated with coronary artery disease (CAD)[10–13] and ischemic stroke[14–16] predisposition, albeit with small individual effects. Exact pathobiological mechanisms leading to cardiovascular symptoms are still poorly understood, but CAD- and ischemic stroke genetic variants were previously associated to atherosclerotic plaque composition.[17]

Polygenic risk scores (PRS) summarize the small individual genetic effects into a quantitative measure of genetic disease susceptibility. Recent studies showed that PRS were strongly correlated with prevalent and incident CAD independent of traditional risk factors including family history.[18,19] For example, individuals with higher scores of the MetaGRS (a PRS for CAD including 1.7 million SNPs) were at 1.7-4.2 fold higher risk for a first coronary event compared to individuals with lower MetaGRS scores. However, studies that have investigated the association of PRS and sCVE are limited and show inconsistent results.[20–26]

In the present study we aimed to study the association between FHx, polygenic risk and long-term secondary cardiovascular outcome in patients undergoing carotid endarterectomy (CEA). Moreover, to explore possible underlying pathophysiological mechanisms, we studied the impact of MetaGRS and FHx on carotid histological plaque characteristics.

Methods

Athero-Express Biobank

All patients in this study were included in the Athero-Express Biobank, a prospective cohort study that included consecutive patients with severe carotid artery stenosis undergoing CEA in two large tertiary referral hospitals in The Netherlands, the University Medical Centre Utrecht (inclusion is ongoing) and the St. Antonius Hospital Nieuwegein (inclusion until 2014).[27] The study design has been published before.[27] In short, patient characteristics, such as demographics, cardiovascular risk factors including medical history, medication use, and FHx for cardiovascular disease, were obtained through standardized questionnaires and checked in electronic health records. Preoperative blood samples were drawn. The atherosclerotic plaque obtained during surgery was collected and immunohistochemically analysed. Patients were followed up for three years after surgery for the occurrence of secondary cardiovascular events through standardized questionnaires and by checking electronic health records. General practitioners were consulted in case of no response to questionnaires or in order to obtain further information regarding reported cardiovascular events. Patients operated for restenosis (6% of 2044 eligible patients for this study) were excluded because these differ in future cardiovascular event risk.[28] Thus for the current study, a total of 1,788 patients operated from March 2002 until July 2016 had available 3-year follow-up data and FHx data, and were included for analysis. Of these, 1,551/1,788 (87%) patients had available histological carotid plaque data. A total of 1,319/1,788 (74%) patients had available genotype data of whom 1,301 (98%) also had histological carotid plaque data. This study was performed according to the Declaration of Helsinki and was approved by the local ethics committee of both hospitals. Patients provided written informed consent before study participation.

Definitions

A positive FHx was defined as having a first-degree relative (either a parent or sibling) with onset of cardiovascular disease (myocardial infarction (MI), coronary artery stenosis, stroke, abdominal aortic aneurysm (AAA), or cardiovascular death including sudden death) before the age of 60 years. The primary outcome of this study was defined as a composite secondary cardiovascular event (sCVE) within three years of follow-up including fatal or non-fatal MI, fatal or non-fatal stroke, ruptured AAA, fatal cardiac failure, coronary or peripheral interventions (either percutaneous or bypass surgery), leg amputation due to cardiovascular causes and cardiovascular death. Secondary outcomes were histological atherosclerotic carotid plaque characteristics.

Genotyping

Methods for genotyping, quality control and imputation in the Athero-Express biobank have been published elsewhere [29,30]. Briefly, DNA was extracted from EDTA whole blood samples or if not present from atherosclerotic plaque tissue according to validated protocols. Genotyping was performed with two commercially available chips: the first batch by Affymetrix Genome-Wide Human SNP array 5.0 (previously used in the Athero-Express Genomics Study 1, covering samples obtained in 2002-2007) and the second batch by Affymetrix Axiom GW CEU 1 array (previously used in Athero-Express Genomics Study 2, covering samples obtained in 2002-2013). Procedures for data quality control and data cleaning were in accordance with global standards.[31] A combined dataset of 1000 Genome (phase 3, version 5) and The Genome of the Netherlands Project release 5 was used as a reference for imputation.[32]

Polygenic risk score (MetaGRS)

To estimate the polygenic burden for cardiovascular disease for included patients, we used the polygenic risk score for CAD (MetaGRS) that was recently published by Inouye and colleagues.[18] The MetaGRS comprises 1.7 million genetic variants associated with CAD and was constructed through meta-analysis of three genomic risk scores: GRS46K (comprising 46,000 cardiometabolic genetic variants), FDR202 (including 202 genetic variants associated with CAD at false discovery rate $p<0.05$ in the recent GWAS CARDIoGRAMplusC4D) and the 1000Genomes genetic score also created with CARDIoGRAMplusC4D. MetaGRS was internally and externally validated for the primary risk of prevalent and incident CAD in the UK Biobank.[18]

Sample handling

After CEA, the atherosclerotic plaque was directly processed in the laboratory following standardized protocols.[4,27,33,34] The plaque was cut in cross-sectional segments of 5mm. The segment with largest plaque burden was chosen as the culprit lesion and immunohistochemically analysed for macrophages, smooth muscle cells (SMC), lipid core, calcification, collagen, intraplaque haemorrhage (IPH) and microvessel content. Extensive description of the standardized protocol for atherosclerotic plaque processing and analysis of plaque characteristics has been previously reported and is added to the Supplemental. [4,27,33,34] To assess the overall vulnerability of the atherosclerotic plaque, a vulnerability score was created ranging from 0-5 with 1 point for plaque characteristics that are considered hallmarks of a vulnerable plaque (moderate/heavy macrophages, no/minor collagen, no/minor SMC, lipid core>10% and presence of IPH), based on a previous publication.[35]

Statistical analysis

Baseline characteristics were compared between patient groups (FHx and MetaGRS) by chi-square test for categorical variables and Student's t-test for continuous variables (lipid levels were log-transformed). We analysed the association between FHx and MetaGRS and sCVE by Cox-proportional hazard regression models and the associations with plaque characteristics through logistic or linear regression models. To fully unravel the genetic association, the association of MetaGRS with sCVE and plaque characteristics was analysed in three ways: (1) MetaGRS as continuous measure (2) patients in the top 20% of the MetaGRS distribution compared to the remaining 80%, and (3) patients in the top 20% of the MetaGRS distribution compared to those in the bottom 20% of the distribution. Kaplan-Meier curves were constructed to graphically illustrate univariate associations. Confounders for multivariable analyses were selected based on literature[18,35,36] (for sCVE these were age, sex, diabetes, BMI, smoking and hypercholesterolemia and for plaque characteristics these were and age, sex, surgery year and type of cerebrovascular symptoms). Additional confounders were added when showing an association of $p<0.20$ with the determinant (FHx or MetaGRS) and outcome of interest (sCVE or plaque characteristics). For MetaGRS models genotype array and principal components 1-4 were also added. Full model description is displayed in the Supplemental Tables S1 and S2. Because a previous study in our biobank showed that IPH is associated with sCVE[4], IPH was added to multivariable models of FHx, MetaGRS and sCVE to explore whether IPH could be one possible underlying mechanism. Sex-stratified analyses were performed to unravel sex-dependent differences in associations. Values with $p<0.05$ were considered statistically significant. All analyses were performed in IBM SPSS Statistics version 25.0.

Results

Patient selection from the Athero-Express Biobank and characteristics of the study population are displayed in Figure 1 and Table 1. Patients had a mean age 69 years and 70% were men. The cohort represented a typically severe atherosclerotic cohort with high prevalence of traditional risk factors and atherosclerotic manifestations in other vascular beds (coronary or peripheral arteries). Baseline characteristics were similar between the total cohort with FHx data and the sub-cohort with genotyped data (Table 1).

Patients with positive FHx have a higher risk of sCVE

Patients with a positive FHx (744/1,788, 41.6%) were younger and had on average more cardiovascular risk factors (Table 1). During a median follow-up of 2.9 years, 418 patients (23.4%) reached the composite endpoint of sCVE (Figure 2A). Patients with positive FHx had an increased risk of sCVE compared to those without (absolute 3-year risks of 26.5% versus 21.2% respectively) hazard ratio (HR) 1.292, 95% confidence interval (CI), 1.066-1.566, p=0.009 (Figure 3; Supplemental Table S3). This association remained significant after correction for confounders with adjusted HR 1.287, 95%CI 1.033-1.604, p=0.024 (Figure 3; Supplemental Table S3) and was independent of genetic predisposition as measured by MetaGRS (adjusted HR 1.397, 95%CI 1.074-1.819, p=0.013, Figure 3; Supplemental Table S3). Sex-stratified analyses confirmed results in men but not in women, although multivariable analyses could not be performed because of limited power (Supplemental Table S3).

Patients with higher MetaGRS have a higher risk of sCVE

The MetaGRS (on a scale from -1.2 to 0.9) approximated a normal distribution in the study population (Supplemental Figure S1). Patients in the top 20% of MetaGRS were relatively more often females, younger of age and had less often diabetes compared to the remaining 80% of the cohort (Table 1). Differences in baseline characteristics between high and low genetic risk patients can be found in the supplemental (Table S4). Patients in the top 20% of MetaGRS had 1.4 fold increased risk of developing sCVE within the three years of follow-up when compared to the remaining 80% of the cohort (HR 1.353, 95%CI 1.047-1.749, p=0.021). After adjustment for possible confounders including FHx this association remained statistically significant (HR for top 20% 1.345, 95% CI 1.009-1.792, p=0.043). We found similar results when we compared patients in top 20% to the bottom 20% of MetaGRS (in univariate analysis with HR 1.539, 95%CI,1.086-2.181, p=0.015 and for multivariable analysis adjusted HR including FHx 1.583, 95%CI, 1.066-2.351, p=0.023) and when analysing MetaGRS as a continuous variable (adjusted for confounders with HR 1.724 per 1 point increase in MetaGRS, 95%CI 1.080-2.752, p= 0.022, adjusted HR including FHx 1.525 per 1 point increase in MetaGRS, 95% CI, 0.937-2.483, p=0.090). Results are illustrated in Figure 3 and displayed in Supplemental Table S3. Confounders added to multivariable models are displayed in Supplemental Tables S1 and S2.

Similar results were found in men (Supplemental Table S3). In women univariate analyses showed no significant associations between MetaGRS and sCVE, yet multivariable analysis was not possible due to lack of power (Supplemental Table S3).

MetaGRS is associated with vulnerable carotid plaque characteristics

To unravel possible underlying pathophysiological mechanisms of the associations between MetaGRS, FHx and CVD, we looked at atherosclerotic plaque characteristics. We found no associations between histological plaque characteristics and FHx in the total cohort or in women although not all multivariable analyses could be performed (Supplemental Table S7 and S8). However carotid plaques from men with a positive FHx contained less collagen and less SMC content compared to men with negative FHx (Supplemental table S8). MetaGRS was associated with significantly higher overall plaque vulnerability score (regression coefficient β of 0.282 per 1-point increase in MetaGRS, 95%CI, 0.014-0.549, p=0.039). To determine the plaque characteristics on which this association was based, plaque characteristics were analysed separately. High genetic risk patients (in top 20% of MetaGRS) more frequently had a lipid core>10% of total plaque area (adjusted odds ratio (OR), 1.591, 95% CI, 1.105-2.291, p=0.013) and more macrophage infiltration (adjusted OR 1.490, 95% CI 1.118-1.986, p=0.006) compared to patients with MetaGRS in the remaining 80% (Table 2). For lipid core, we found the same association when comparing the top 20% with the bottom 20% of the MetaGRS (adjusted HR 1.887, 95% CI, 1.188-2.997, p=0.007, Supplemental Table S5). Looking at MetaGRS as a continuous variable, in addition we found an association with IPH (adjusted OR 1.652, 95%CI, 1.018-2.680, p=0.042) (table 3). Sex-stratified analyses revealed a significant association of MetaGRS with macrophages in women (adjusted OR per 1 point increase in MetaGRS 2.372, 95%CI, 1.036-5.429, p=0.041) whereas a significant association of MetaGRS with IPH was found in men (adjusted OR per 1 point increase 2.277, 95%CI, 1.242-4.176, p=0.008, Supplemental Table S6).

Because IPH has been associated with increased risk of sCVE[4], we added IPH to the multivariable models of FHx, MetaGRS and sCVE to unravel whether the association between FHx, MetaGRS and sCVE could be explained by IPH. We found that all associations were independent of IPH as addition of IPH to multivariable models of sCVE did not alter the effect sizes (Supplemental Table S3).

Discussion

We investigated the associations of FHx and polygenic risk score for CAD (MetaGRS) with sCVE after CEA. We report four key findings. First, FHx was independently associated with an increased risk of sCVE. Second, higher MetaGRS score was independently associated with an increased risk of sCVE. Third, the association of MetaGRS with sCVE was independent of FHx and the association of FHx with sCVE was independent of MetaGRS. Fourth, high MetaGRS was associated with a more vulnerable carotid atherosclerotic plaque suggesting possible underlying pathobiological mechanisms through which genetic variants could affect CVD.

Although positive FHx is a well-known risk factor for primary CVE[1,2], previous studies assessing FHx and secondary outcome are inconsistent.[5,7–9,37] In patients with first-MI[7,8,37], studies have reported a protective effect of FHx on all-cause mortality, whereas others showed an increased risk of CVE.[5,9] One can assume that patients with positive FHx are identified earlier as at-risk individuals through screening programs resulting in more intensive surveillance and preventive strategies leading to the benefit in overall survival.[7] Indeed, in our cohort patients with positive FHx were also younger at timing of CEA. Of note, it is known that the sensitivity of self-reported FHx can be low (50%-70%) and might therefore be an unreliable estimate.[38]

We found that MetaGRS was associated with a higher risk of sCVE. It is worth noting that MetaGRS comprises genetic susceptibility for primary CAD, whereas we studied sCVE in any vascular bed in patients having carotid stenosis and additional CVD comorbidities. Our results therefore underscore the concept of atherosclerosis as a systemic disease underlying CVD. Indeed, a genomic risk score (GRS) of CAD (300-SNP-CAD-GRS) was associated with

the development of stroke, peripheral artery disease (PAD) and AAA indicating shared genetic roots.[39]

Results from previous studies also assessing GRS and sCVE are conflicting.[21–26] In patients with acute coronary syndrome (ACS) a 30-SNP-GRS was not associated with sCVE after 1 year[22], yet early post-ACS events may have different less genetically-mediated aetiologies (e.g. stent thrombosis or restenosis).[22] Others have reported significant associations of CAD-GRSs and increased risk of sCVE.[24–26] In CAD patients, those in the upper GRS quartile (19-SNP) had higher 10-year risk for CVE compared to the ones in the lowest GRS quartile.[24] In ACS patients, the 47-SNP-GRS was associated with an increased 5.5 year risk of recurrent ACS.[25] Similarly, ACS patients in the top quintile of 27-SNP-GRS had increased 2-year risk of ACS and coronary death compared to those with intermediate (quintiles 2-4) or low genetic risk (lowest quintile) independent of cardiovascular risk factors including FHx. [26] Of note, previous studies used PRS with limited number of SNPs (varying from 19 to 47 SNPs) and predominantly studied CAD patients.[21,22,24,25] The MetaGRS used in the current study is constructed through meta-analysis and therefore captures the totality of information obtained until now from GWAS and consecutive GRS for CAD and is the first study revealing its association with sCVE in CEA patients.[18] Interestingly, no studies have investigated sex-differences in the association between PRS and sCVE. We confirm the associations of MetaGRS, FHx and sCVE in men, but in women these associations remain unclear because we lacked sufficient power for multivariable analysis.

Previous studies scarcely incorporated FHx[21–25] except for one.[26] We confirm the independent association of MetaGRS with sCVE from FHx. Furthermore, we found that positive

FHx was associated with increased risk of sCVE independent of genetic risk, which has not been reported before. Several reasons could be hypothesized for the non-overlapping associations of FHx and MetaGRS with CVE. MetaGRS includes common genetic variants associated to an increased risk for CAD in the general population, whilst CVD in families may arise in part from more rare genetic variants, and thus a positive FHx capture individual rare variation. Another explanation could be that FHx reflects not only genetic factors but also non-genetic factors. Although we corrected for traditional risk factors, other environmental factors that were not taken into account such as social economic status or nutrition patterns could still be attributable to the risk of secondary events.

Exactly how genetic variants affect CVD is currently unknown. CAD-variants have been linked to pathways involved in atherosclerosis (e.g. lipid metabolism, inflammation, blood pressure and vascular remodelling), but most CAD-variants are situated outside protein-coding regions with unknown functions, making them hard to map to pathophysiological mechanisms.[13,40] We found that MetaGRS was associated with more rupture-prone atherosclerotic plaque displayed by a higher plaque vulnerability score caused by more fat, IPH (predominantly in men) and macrophages (predominantly in women). Moreover, carotid plaques from men with positive FHx were associated with less SMC and less collagen, whereas the association in women remains unclear. Similarly, a previous AE study showed that a CAD-PRS was correlated with more fat, whereas a large-artery stroke-PRS was correlated with more IPH and SMC.[17] Our results support the view that genetic variants could mediate their effect on CVD by influencing atherosclerotic plaque composition. Interestingly, IPH has been associated with sCVE in men independent of other clinical risk factors in our biobank [4,41], yet we found that the

associations of MetaGRS, FHx and sCVE were independent of IPH. It therefore remains unclear what the underlying mechanism is through which MetaGRS and FHx exert their increased sCVE risk. Future studies should explore exact pathophysiological mechanisms how genetic variants captured by the MetaGRS influence plaque destabilization, primary and secondary CVE risk, for example through deep-phenotyping of atherosclerotic plaque characteristics by quantitative computerized analysis[42] or mapping MetaGRS loci to specific CVE (MI, stroke or PAD). Also, a possible sex-difference needs to be addressed.

Although PRS could identify high-risk patients for CVE, one could assume that due to their unfavourable genetic risk the CVE risk is unchangeable. However, previous studies have suggested that high genetic risk is modifiable by lifestyle interventions or medication. Among individuals with high genetic risk (top 20% of CAD-GRS), those adhering to a healthy lifestyle had lower relative risk of a first-CAD event compared to those with an unfavourable lifestyle. [43] Moreover, both in primary or secondary prevention trials, patients with high genetic risk (those in top 20% of CAD-GRS) had a greater absolute and relative risk reduction of (recurrent) MI or coronary death than those with lower genetic risk despite equal LDL level reductions. [26,44] In the current era of evolving new expensive drugs (e.g. PCSK9-inhibitors or new anti-inflammatory drugs such as IL1b-blockers[45]) and the increasing burden of CVD on the sustainability of the healthcare system, the cost-effectiveness ratio becomes important. In the future, it may be useful to investigate whether the efficacy of such medications varies across genetic risk categories for selecting those benefit most and qualify for these add-on therapies.

Admittedly, our study has several limitations. First, we did not have data regarding medication use during follow-up nor therapy compliance. These factors could have interfered with observed sCVE rates. Second, owing to limited power we were unable to assess associations with separate CVE or determine the predictive value of MetaGRS above clinical risk factors. Third, we could not exclude possible sex-dependent differences because we did not have adequate number of women for multivariable analysis. Last, most included patients are of European ancestries and generalizability to other ethnicities needs further attention. Still, this is the first study on MetaGRS and sCVE with unique data on FHx and plaque characteristics in a cohort with symptomatic carotid artery stenosis.

In the future, PRS may be a useful tool for personalized risk prediction for primary or secondary CVE. Adding MetaGRS to a model with traditional risk factors improved prediction of first-CAD events, although model improvement was modest.[18] The clinical utility of PRS for sCVE is still unknown because the incremental value of PRS above clinical factors still needs to be established. One study suggested an additive predictive value of PRS above clinical factors but did not include FHx [24], whereas other studies failed to demonstrate this.[22,23,25] The power of these studies may have been limited due to limited number of CVE. Pooling data of several cohorts including detailed data on preventive strategies and medications during follow-up together with use of uniform outcome definitions for sCVE and uniform PRS composition could help elucidate the clinical value of PRS, for example within international collaborations such as the GENIUS-CHD Consortium.[46]

In conclusion, both higher MetaGRS and positive FHx were independently associated with increased risk of sCVE in severe atherosclerotic patients with manifest CVD. Higher MetaGRS was also associated with more vulnerable carotid plaque characteristics indicating possible underlying mechanism how genetic variants influence CVD. PRS could identify high-risk individuals and may help selecting future study populations when investigating new therapeutic CVD prevention strategies.

Acknowledgements

We thank Sara van Laar, Sara Bregman, Bram Vermeulen, Evelyn Velema and Joelle van Bennekom for their technical support in the Athero-Express Biobank.

Conflict of interest statement:

none

Financial support

Dr. van der Laan was funded through grants from the Netherlands CardioVascular Research Initiative of the Netherlands Heart Foundation (CVON 2011/B019 and CVON 2017-20: Generating the best evidence-based pharmaceutical targets for atherosclerosis [GENIUS I&II]). Dr. Timmerman, Dr. De Borst, dr. De Kleijn, and dr. Pasterkamp are funded through the EU 755320 Taxinomisis grant. We acknowledge the European Research Area Network on Cardiovascular diseases (ERA-CVD, grant number 01KL1802). There are no competing interests declared.

Author contributions

Study design: NT, SH, SWvdL

Data collection: NT, SH, SWvdL, GP

Data analysis and interpretation: NT, SH, SWvdL

Drafting the article and figures: NT, SH, SWvdL

Critical revision and final approval: NT, SH, SWvdL, DPVdK, GJB, HMdR, FWA, GP

References

1. Lloyd-Jones DM, Nam B-H, D'Agostino, Sr RB, Levy D, Murabito JM, Wang TJ, Wilson PWF, O'Donnell CJ. Parental Cardiovascular Disease as a Risk Factor for Cardiovascular Disease in Middle-aged Adults. *JAMA* 2004;291:2204-2211.
2. Chow CK, Islam S, Bautista L, Rumboldt Z, Yusufali A, Xie C, Anand SS, Engert JC, Rangarajan S, Yusuf S. Parental history and myocardial infarction risk across the world: The INTERHEART study. J Am Coll Cardiol 2011;57:619-27.
3. Berg MJ van den, Bhatt DL, Kappelle LJ, Borst GJ de, Cramer MJ, Graaf Y van der, Steg PG, Visseren FLJ. Identification of vascular patients at very high risk for recurrent cardiovascular events: validation of the current ACC/AHA very high risk criteria. Eur Heart J 2017;38:3211–3218.
4. Hellings WE, Peeters W, Moll FL, Piers SRD, Setten J van, Spek PJ Van der, Vries JPPM de, Seldenrijk KA, Bruin PC De, Vink A, Velema E, Kleijn DP V de, Pasterkamp G. Composition of carotid atherosclerotic plaque is associated with cardiovascular outcome: a prognostic study. Circulation 2010;121:1941–1950.
5. Mulders TA, Meyer Z, Donk C van der, Kroon AA, Ferreira I, Stehouwer CDA, Pinto-Sietsma SJ. Patients with premature cardiovascular disease and a positive family history for cardiovascular disease are prone to recurrent events. Int J Cardiol 2011;153:64–67.
6. Canto JG, Kiefe CI, Rogers WJ, Peterson ED, Frederick PD, French WJ, Gibson CM, Pollack C V., Ornato JP, Zalenski RJ, Penney J, Tiefenbrunn AJ, Greenland P. Atherosclerotic risk factors and their association with hospital mortality among patients with first myocardial infarction (from the national registry of myocardial infarction). Am J Cardiol 2012;110:1256–1261.

7. Abdi-Ali A, Shaheen A, Southern D, Zhang M, Knudtson M, White J, Graham M, James MT, Wilton SB. Relation Between Family History of Premature Coronary Artery Disease and the Risk of Death in Patients With Coronary Artery Disease. Am J Cardiol 2016;117:353–358.

8. Harpaz D, Behar S, Rozenman Y, Boyko V, Gottlieb S, Israeli Working Group on Intensive Cardiac Care IHS. Family History of Coronary Artery Disease and Prognosis after First Acute Myocardial Infarction in a National Survey. Cardiology 2004;102:140–146.

9. Kim C, Chang H-J, Cho I, Sung JM, Choi D, Jeong MH, Jang YS, Korea Acute Myocardial Infarction Registry Investigators OKAMIR. Impact of family history on the presentation and clinical outcomes of coronary heart disease: data from the Korea Acute Myocardial Infarction Registry. Korean J Intern Med 2013;28:547–556.

10. Nikpay M, Goel A, Won H-H, Hall LM, Willenborg C, Kanoni S, Saleheen D, Kyriakou T, Nelson CP, Hopewell JC, Webb TR, Zeng L, Dehghan A, Alver M, Armasu SM, Auro K, Bjonnes A, Chasman DI, Chen S, Ford I, Franceschini N, Gieger C, Grace C, Gustafsson S, Huang J, Hwang S-J, Kim YK, Kleber ME, Lau KW, et al. A comprehensive 1000 Genomes–based genome-wide association meta-analysis of coronary artery disease. Nat Genet 2015;47:1121–1130.

11. Howson JMM, Zhao W, Barnes DR, Ho W-K, Young R, Paul DS, Waite LL, Freitag DF, Fauman EB, Salfati EL, Sun BB, Eicher JD, Johnson AD, Sheu WHH, Nielsen SF, Lin W-Y, Surendran P, Malarstig A, Wilk JB, Tybjærg-Hansen A, Rasmussen KL, Kamstrup PR, Deloukas P, Erdmann J, Kathiresan S, Samani NJ, Schunkert H, Watkins H, Do R, Rader DJ, et al. Fifteen new risk loci for coronary artery disease highlight arterial-wall-

specific mechanisms. Nat Genet 2017;49:1113–1119.

12. Verweij N, Eppinga RN, Hagemeijer Y, Harst P van der. Identification of 15 novel risk loci for coronary artery disease and genetic risk of recurrent events, atrial fibrillation and heart failure. Sci Rep 2017;**7**:2761.

13. Erdmann J, Kessler T, Munoz Venegas L, Schunkert H. A decade of genome-wide association studies for coronary artery disease: the challenges ahead. Cardiovasc Res 2018;**114**:1241–1257.

14. Traylor M, Farrall M, Holliday EG, Sudlow C, Hopewell JC, Cheng Y-C, Fornage M, Ikram MA, Malik R, Bevan S, Thorsteinsdottir U, Nalls MA, Longstreth W, Wiggins KL, Yadav S, Parati EA, Destefano AL, Worrall BB, Kittner SJ, Khan MS, Reiner AP, Helgadottir A, Achterberg S, Fernandez-Cadenas I, Abboud S, Schmidt R, Walters M, Chen W-M, Ringelstein EB, O'Donnell M, et al. Genetic risk factors for ischaemic stroke and its subtypes (the METASTROKE collaboration): a meta-analysis of genome-wide association studies. Lancet Neurol 2012;11:951–962.

15. Holliday EG, Maguire JM, Evans T-J, Koblar SA, Jannes J, Sturm JW, Hankey GJ, Baker R, Golledge J, Parsons MW, Malik R, McEvoy M, Biros E, Lewis MD, Lincz LF, Peel R, Oldmeadow C, Smith W, Moscato P, Barlera S, Bevan S, Bis JC, Boerwinkle E, Boncoraglio GB, Brott TG, Brown RD, Cheng Y-C, Cole JW, Cotlarciuc I, Devan WJ, et al. Common variants at 6p21.1 are associated with large artery atherosclerotic stroke. Nat Genet 2012;44:1147–1151.

16. Malik R, Traylor M, Pulit SL, Bevan S, Hopewell JC, Holliday EG, Zhao W, Abrantes P, Amouyel P, Attia JR, Battey TWK, Berger K, Boncoraglio GB, Chauhan G, Cheng Y-C, Chen W-M, Clarke R, Cotlarciuc I, Debette S, Falcone GJ, Ferro JM, Gamble DM, Ilinca

A, Kittner SJ, Kourkoulis CE, Lemmens R, Levi CR, Lichtner P, Lindgren A, Liu J, et al. Low-frequency and common genetic variation in ischemic stroke. Neurology 2016;86:1217–1226.

17. Laan SW van der, Siemelink MA, Haitjema S, Foroughi Asl H, Perisic L, Mokry M, Setten J van, Malik R, Dichgans M, Worrall BB, Samani NJ, Schunkert H, Erdmann J, Hedin U, Paulsson-Berne G, Björkegren JLM, Borst GJ de, Asselbergs FW, Ruijter HM Den, Bakker PIW de, Pasterkamp G, Pasterkamp G. Genetic Susceptibility Loci for Cardiovascular Disease and Their Impact on Atherosclerotic Plaques. Circ Genomic Precis Med 2018;11:e002115.

18. Inouye M, Abraham G, Nelson CP, Wood AM, Sweeting MJ, Dudbridge F, Lai FY, Kaptoge S, Brozynska M, Wang T, Ye S, Webb TR, Rutter MK, Tzoulaki I, Patel RS, Loos RJF, Keavney B, Hemingway H, Thompson J, Watkins H, Deloukas P, Angelantonio E Di, Butterworth AS, Danesh J, Samani NJ, UK Biobank CardioMetabolic Consortium CHD Working Group. Genomic Risk Prediction of Coronary Artery Disease in 480,000 Adults: Implications for Primary Prevention. J Am Coll Cardiol;018;72:1883–1893.

19. Khera A V, Chaffin M, Aragam KG, Haas ME, Roselli C, Choi SH, Natarajan P, Lander ES, Lubitz SA, Ellinor PT, Kathiresan S. Genome-wide polygenic scores for common diseases identify individuals with risk equivalent to monogenic mutations. Nat Genet 2018;**50**:1219–1224.

20. Tragante V, Doevendans PAFM, Nathoe HM, Graaf Y van der, Spiering W, Algra A, Borst GJ de, Bakker PIW de, Asselbergs FW. The impact of susceptibility loci for coronary artery disease on other vascular domains and recurrence risk. Eur Heart

J;2013;34:2896–2904.

21. Christiansen MK, Nyegaard M, Larsen SB, Grove EL, Würtz M, Neergaard-Petersen S, Hvas A-M, Jensen HK, Kristensen SD. A genetic risk score predicts cardiovascular events in patients with stable coronary artery disease. Int J Cardiol 2017;241:411–416.

22. Labos C, Martinez SC, Leo Wang RH, Lenzini PA, Pilote L, Bogaty P, Brophy JM, Engert JC, Cresci S, Thanassoulis G. Utility of a genetic risk score to predict recurrent cardiovascular events 1 year after an acute coronary syndrome: A pooled analysis of the RISCA, PRAXY, and TRIUMPH cohorts. Atherosclerosis 2015;242:261–267.

23. Weijmans M, Bakker PIW de, Graaf Y van der, Asselbergs FW, Algra A, Jan de Borst G, Spiering W, Visseren FLJ. Incremental value of a genetic risk score for the prediction of new vascular events in patients with clinically manifest vascular disease. Atherosclerosis 2015;239:451–458.

24. Wirtwein M, Melander O, Sjőgren M, Hoffmann M, Narkiewicz K, Gruchala M, Sobiczewski W. Relationship between selected DNA polymorphisms and coronary artery disease complications. Int J Cardiol 2017;228:814–820.

25. Vaara S, Tikkanen E, Parkkonen O, Lokki M-L, Ripatti S, Perola M, Nieminen MS, Sinisalo J. Genetic Risk Scores Predict Recurrence of Acute Coronary Syndrome. Circ Cardiovasc Genet 2016;9:172–178.

26. Mega JL, Stitziel NO, Smith JG, Chasman DI, Caulfield MJ, Devlin JJ, Nordio F, Hyde CL, Cannon CP, Sacks FM, Poulter NR, Sever PS, Ridker PM, Braunwald E, Melander O, Kathiresan S, Sabatine MS. Genetic risk, coronary heart disease events, and the clinical benefit of statin therapy: an analysis of primary and secondary prevention trials. Lancet 2015;385:2264–2271.

27. Verhoeven BAN, Velema E, Schoneveld AH, Vries JPPM de, Bruin P de, Seldenrijk CA, Kleijn DP V de, Busser E, Graaf Y van der, Moll F, Pasterkamp G. Athero-express: differential atherosclerotic plaque expression of mRNA and protein in relation to cardiovascular events and patient characteristics. Rationale and design. Eur J Epidemiol 2004;19:1127–1133.

28. Kumar R, Batchelder A, Saratzis A, AbuRahma AF, Ringleb P, Lal BK, Mas JL, Steinbauer M, Naylor AR. Restenosis after Carotid Interventions and Its Relationship with Recurrent Ipsilateral Stroke: A Systematic Review and Meta-analysis. Eur J Vasc Endovasc Surg 2017;53:766–775.

29. Laan SW van der, Foroughi Asl H, Borne P van den, Setten J van, Perk MEM van der, Weg SM van de, Schoneveld AH, Kleijn DPV de, Michoel T, Björkegren JLM, Ruijter HM den, Asselbergs FW, Bakker PIW de, Pasterkamp G. Variants in ALOX5, ALOX5AP and LTA4H are not associated with atherosclerotic plaque phenotypes: The Athero-Express Genomics Study. Atherosclerosis 2015;239:528–538.

30. Siemelink MA, Laan SW van der, Setten J van, Vries JPPM de, Borst GJ de, Moll FL, Ruijter HM den, Asselbergs FW, Pasterkamp G, Bakker PIW de. Common variants associated with blood lipid levels do not affect carotid plaque composition. Atherosclerosis 2015;242:351–356.

31. Anderson CA, Pettersson FH, Clarke GM, Cardon LR, Morris AP, Zondervan KT. Data quality control in genetic case-control association studies. Nat Protoc 2010;5:1564–1573.

32. Genome of the Netherlands Consortium, Francioli LC, Menelaou A, Pulit SL, Dijk F van, Palamara PF, Elbers CC, Neerincx PBT, Ye K, Guryev V, Kloosterman WP, Deelen P, Abdellaoui A, Leeuwen EM van, Oven M van, Vermaat M, Li M, Laros JFJ, Karssen LC,

Kanterakis A, Amin N, Hottenga JJ, Lameijer E-W, Kattenberg M, Dijkstra M, Byelas H, Setten J van, Schaik BDC van, Bot J, Nijman IJ, et al. Whole-genome sequence variation, population structure and demographic history of the Dutch population. Nat Genet 2014;46:818–825.

33. Vrijenhoek JEP, Nelissen BGL, Velema E, Vons K, Vries J-PPM de, Eijkemans MJC, Ruijter HM den, Borst GJ de, Moll FL, Pasterkamp G. High Reproducibility of Histological Characterization by Whole Virtual Slide Quantification; An Example Using Carotid Plaque Specimens. PLoS One 2014;9:e115907.

34. Hellings WE, Pasterkamp G, Vollebregt A, Seldenrijk CA, Vries JPPM De, Velema E, Kleijn DPV De, Moll FL. Intraobserver and interobserver variability and spatial differences in histologic examination of carotid endarterectomy specimens. J Vasc Surg 2007;46:1147–1154.

35. Verhoeven B, Hellings WE, Moll FL, Vries JP de, Kleijn DPV de, Bruin P de, Busser E, Schoneveld AH, Pasterkamp G. Carotid atherosclerotic plaques in patients with transient ischemic attacks and stroke have unstable characteristics compared with plaques in asymptomatic and amaurosis fugax patients. J Vasc Surg 2005;42:1075–1081.

36. Lammeren GW van, Ruijter HM den, Vrijenhoek JEP, Laan SW van der, Velema E, Vries JPPM de, Kleijn DP V. de, Vink A, Borst GJ de, Moll FL, Bots ML, Pasterkamp G. Time-Dependent Changes in Atherosclerotic Plaque Composition in Patients Undergoing Carotid Surgery. Circulation 2014;129:2269–2276.

37. Canto JG, Kiefe CI, Rogers WJ, Peterson ED, Frederick PD, French WJ, Gibson CM, Pollack C V., Ornato JP, Zalenski RJ, Penney J, Tiefenbrunn AJ, Greenland P. Number of coronary heart disease risk factors and mortality in patients with first myocardial

infarction. *JAMA* 2011;306:2120-2127.

38. Murabito JM, Nam B-H, D'Agostino RB, Lloyd-Jones DM, O'Donnell CJ, Wilson PWF. Accuracy of Offspring Reports of Parental Cardiovascular Disease History: The Framingham Offspring Study. Ann Intern Med 2004;140:434–440.

39. Ntalla I, Kanoni S, Zeng L, Giannakopoulou O, Danesh J, Watkins H, Samani NJ, Deloukas P, Schunkert H. Genetic Risk Score for Coronary Disease Identifies Predispositions to Cardiovascular and Noncardiovascular Diseases. J Am Coll Cardiol 2019;73:2932–2942.

40. Haitjema S, Meddens CA, Laan SW van der, Kofink D, Harakalova M, Tragante V, Foroughi Asl H, Setten J van, Brandt MM, Bis JC, O'Donnell C, Cheng C, Hoefer IE, Waltenberger J, Biessen E, Jukema JW, Doevendans PAFM, Nieuwenhuis EES, Erdmann J, Björkegren JLM, Pasterkamp G, Asselbergs FW, Ruijter HM den, Mokry M. Additional Candidate Genes for Human Atherosclerotic Disease Identified Through Annotation Based on Chromatin Organization. Circ Cardiovasc Genet 2017;10:e001664.

41. Vrijenhoek JEP, Ruijter HM Den, Borst GJ De, Kleijn DP V de, Vries J-PPM De, Bots ML, Weg SM Van de, Vink A, Moll FL, Pasterkamp G. Sex is associated with the presence of atherosclerotic plaque hemorrhage and modifies the relation between plaque hemorrhage and cardiovascular outcome. Stroke 2013;44:3318–3323.

42. Nelissen BGL, Herwaarden JA van, Moll FL, Diest PJ van, Pasterkamp G. SlideToolkit: an assistive toolset for the histological quantification of whole slide images. PLoS One 2014;9:e110289.

43. Khera AV, Emdin CA, Drake I, Natarajan P, Bick AG, Cook NR, Chasman DI, Baber U, Mehran R, Rader DJ, Fuster V, Boerwinkle E, Melander O, Orho-Melander M, Ridker

PM, Kathiresan S. Genetic Risk, Adherence to a Healthy Lifestyle, and Coronary Disease. N Engl J Med 2016;375:2349–2358.

44. Natarajan P, Young R, Stitziel NO, Padmanabhan S, Baber U, Mehran R, Sartori S, Fuster V, Reilly DF, Butterworth A, Rader DJ, Ford I, Sattar N, Kathiresan S. Polygenic Risk Score Identifies Subgroup With Higher Burden of Atherosclerosis and Greater Relative Benefit From Statin Therapy in the Primary Prevention Setting. Circulation 2017;135:2091–2101.

45. Ridker PM, Everett BM, Thuren T, MacFadyen JG, Chang WH, Ballantyne C, Fonseca F, Nicolau J, Koenig W, Anker SD, Kastelein JJP, Cornel JH, Pais P, Pella D, Genest J, Cifkova R, Lorenzatti A, Forster T, Kobalava Z, Vida-Simiti L, Flather M, Shimokawa H, Ogawa H, Dellborg M, Rossi PRF, Troquay RPT, Libby P, Glynn RJ. Antiinflammatory Therapy with Canakinumab for Atherosclerotic Disease. N Engl J Med 2017;377:1119–1131.

46. Patel RS, Asselbergs FW. The GENIUS-CHD consortium. Eur Heart J 2015;36:2674–2676.

Figure Legends

Figure 1-Flowchart.

Figure 2. Kaplan-Meier graphs for 3-year risk of sCVE.

A. Patients with positive FHx compared to those without.
B. Patients in the top 20% of MetaGRS compared to the rest of the patients (remaining 80%).
C. Patients in the top 20% of MetaGRS compared to those in the bottom 20% of MetaGRS.

Figure 3. Cox-regression analyses of FHx and MetaGRs for sCVE.

Hazard ratio's and 95% confidence intervals (95% CI) for the different univariate and multivariable Cox-regression models of FHx or MetaGRS for sCVE.

UV, univariate model. The univariate model for MetaGRS included age, sex, PC1-4 and genotype array.

MV, multivariable model.

The multivariable model for FHx was corrected for traditional risk factors (age, sex, hypercholesterolemia, diabetes, hypertension, BMI and smoking) and additional confounders (history of CAD, history of PAD, cerebrovascular symptoms and eGFR).

The univariate model for MetaGRS included age, sex, PC1-4 and genotype array. For multivariable analyses of MetaGRS traditional risk factors (hypercholesterolemia, diabetes, hypertension, BMI and smoking) were added.

Tables

	Cohort with data on FHx				Sub cohort with genotype data			
	Total (n=1,788)	Negative FHx (n= 1,044)	Positive FHx (n=744)	p-value	Total (n=1,319)	Lower 80% MetaGRS (n=1,055)	Upper 20% MetaGRS (n=264)	p-value
Age (mean, SD)	68.9 [9.1]	70.1 [9.0]	67.1 [8.9]	**2.754 E-12*** [b]	68.7 [9.3]	69.1 [9.1]	67.1 [9.7]	**0.002*** [b]
Male	1244 (69.6)	745 (71.4)	499 (67.1)	0.052 [b]	914 (69.3)	748 (70.9)	166 (62.9)	**0.012*** [b]
BMI (mean, SD)	26.4 [3.9]	26.2 [3.7]	26.8 [4.2]	**0.002*** [b]	26.3 [3.8]	26.2 [3.6]	26.7 [4.3]	0.103 [b]
GFR (mean, SD)	73 [20.8]	72.6 [21.0]	74.1 [20.5]	0.146 [b]	72.3 [20.1]	72.2 [20.1]	72.7 [20.2]	0.744
Smoking	604 (34.0)	341 (33.0)	263 (35.4)	0.286	456 (35.2)	359 (34.6)	97 (37.5)	0.387
Diabetes	390 (21.8)	220 (21.1)	170 (22.8)	0.370	303 (23.0)	255 (24.2)	48 (18.2)	**0.039*** [b]
Hypertension	1,306 (74.4)	728 (71.4)	578 (78.4)	**0.001*** [b]	921 (72.2)	729 (71.8)	192 (74.1)	0.445
Hypercholesterolemia	1,162 (65.0)	637(64.0)	525 (73.9)	**1.500 E-5*** [b]	806 (65.9)	634 (65.1)	172 (69.1)	0.237
History of CAD	535 (29.9)	248 (23.8)	287 (38.6)	**1.327 E-11*** [b]	389 (29.5)	306 (29.0)	83 (31.6)	0.422
History of stroke	574 (32.1)	365 (35.0)	209 (28.1)	**0.002*** [b]	437 (33.1)	348 (33.0)	89 (33.7)	0.823
History of PAD	355 (19.9)	185 (17.7)	170 (22.9)	**0.006*** [b]	270 (20.5)	216 (20.5)	54 (20.5)	0.989
Stenosis ipsilateral				0.083 [b]				0.990
Φ 50-70%	132 (7.5)	70 (6.9)	62 (8.5)		83 (6.4)	66 6.4)	17 (6.6)	
Φ 70-99%	1609 (91.9)	941 (92.3)	668 (91.4)		1200 (93.2)	962 (93.2)	238 (93.0)	
Contralateral stenosis of 50-100%	714 (39.9)	406 (43.1)	308 (45.4)	0.362	543 (45.4)	425 (44.4)	118 (49.4)	0.168 [b]
Presenting symptoms				**0.010*** [b]				0.497
Φ Asymptomatic	228 (12.8)	120 (11.6)	108 (14.6)		178 (13.5)	135 (12.8)	43 (16.3)	
Φ Ocular	302 (16.9)	174 (16.8)	128 (17.3)		203 (15.4)	163 (15.5)	40 (15.2)	
Φ TIA	774 (43.3)	437 (42.2)	337(45.5)		580 (44.1)	466 (44.3)	114 (43.3)	
Φ Stroke	472(26.4)	304 (29.4)	168 (22.7)		354 (26.9)	288 (27.4)	66 (25.1)	
Total cholesterol (median, IQR)	4.4 [1.6]	4.4 [1.6]	4.4 [1.7]	0.140 [b]	4.4 [1.6]	4.4 [1.6]	4.4 [1.7]	0.716
LDL cholesterol (median, IQR)	2.4 [1.3]	2.4 [1.3]	2.5 [1.4]	0.101 [b]	2.4 [1.3]	2.4 [1.3]	2.5 [1.4]	0.330
HDL cholesterol (median, IQR)	1.1 [0.4]	1.1 [0.4]	1.1 [0.4]	0.785	1.1 [0.4]	1.1 [0.4]	1.1 [0.4]	0.384

Triglycerides (median, IQR)	1.5 [1.0]	1.4 [0.9]	1.6 [1.0]	**0.001*** [b]	1.5 [1.0]	1.5 [1.0]	1.5 [0.9]	0.491
Lipid lowering drug use	1,379 (77.1)	779 (74.6)	600 (80.8)	**0.002*** [b]	999 (75.9)	795 (75.5)	204 (77.3)	0.547
Antiplatelet drug use	1,583 (88.5)	926 (88.8)	657(88.5)	0.876	1164 (88.5)	928 (88.3)	236 (89.4)	0.617
Surgery year				0.612				0.820
Φ 2002-2003	215 (12)	129 (11.6)	86 (11.6)		192 (14.6)	151 (14.3)	41 (15.5)	
Φ 2004-2005	327 (18.3)	197 (18.9)	130 (17.5)		307 (23.3)	243 (23.0)	64 (24.2)	
Φ 2006-2007	288 (16.1)	156 (14.9)	132 (17.7)		270 (20.5)	214 (20.3)	56 (21.2)	
Φ 2008-2009	241 (13.5)	146 (14.0)	95 (12.8)		232 (17.6)	185 (17.5)	47 (17.8)	
Φ 2010-2011	265 (14.8)	155 (14.8)	110 (14.8)		224 (17.0)	182 (17.3)	42 (15.9)	
Φ 2012-2013	260 (14.5)	157 (15.0)	103 (13.8)		94 (7.1)	80 (7.6)	14 (5.3)	
Φ 2014-2015	154 (8.6)	82 (7.9)	72 (9.7)		-	-		
Φ 2016	38 (2.1)	22 (2.1)	16 (2.2)		-	-		

Table 1. Baseline characteristics.

Values are displayed as n (%), unless otherwise specified. Values indicated as bold* are statistically significant. Values below p<0.20 are indicated by [b].

BMI, Body mass index; *CAD*, coronary artery disease; *PAD*, peripheral artery disease; *eGFR*, estimated glomerular filtration rate; *TIA*, transient ischemic attack*; SD*, standard deviation. When multiple cerebrovascular symptoms occurred in the six months prior to the operation, the most serious symptom counts in the following order: stroke> TIA> ocular. Ocular symptoms include transient or permanent retinal ischemia.

History of any stroke includes ipsilateral or contralateral stroke. Antiplatelet drug use includes the use of aspirin, dipyridamole or any ADP-inhibitor. Lipid lowering drug use includes any lipid-lowering drug. Diabetes, hypercholesterolemia and hypertension were defined as diagnosed by a medical doctor or medication use for the specific comorbidity.

Categorical plaque characteristics	80% of MetaGRS (n=1,040)	Top 20% of MetaGRS (n=261)	Unadjusted OR (95% CI)	Unadjusted p-value	Adjusted OR (95% CI)	Adjusted p-value
Moderate/heavy calcifications	525/1,038 (50.6)	135/261 (51.7)	1.047 (0.798-1.374)	0.741	1.001 (0.754-1.330)	0.995
Moderate/heavy collagen	826/1,039 (79.5)	211/261 (80.8)	1.088 (0.772-1.534)	0.629	1.091 (0.755-1.577)	0.644
Presence of lipid core >10%	752/1,040 (72.3)	209/261 (80.1)	1.539 (1.104-2.147)	**0.011***	1.591 (1.105-2.291)	**0.013***
Presence of IPH	624/1,039 (60.1)	160/261 (61.3)	1.054 (0.798-1.392)	0.713	1.112 (0.821-1.506)	0.493
Moderate/heavy smooth muscle cells	736/1,037 (71.0)	185/260 (71.2)	1.009 (0.747-1.362)	0.954	0.908 (0.652-1.265)	0.570
Moderate/heavy macrophages	545/1,036 (52.6)	161/260 (61.9)	1.465 (1.109-1.936)	**0.007***	1.490 (1.118-1.986)	**0.006***
Continuous plaque characteristics			**Unadjusted beta (95% CI)**	**Unadjusted p-value**	**Adjusted beta (95% CI)**	**Adjusted p-value**
Number of macrophages (median, IQR)	0.3 [1.0]	0.5 [1.1]	0.058 [-0.006-0.123]	0.077	0.055 (-0.012-0.121)	0.107
Number of smooth muscle cells (median, IQR)	1.4 [2.3]	1.3 [2.3]	-0.010 [-0.095-0.076]	0.822	-0.056 (-0.143-0.031)	0.209
Microvessels (median, IQR)	7.0 [7.0]	7.3 [7.0]	0.088 [-0.021-0.197]	0.114	0.072 (-0.037-0.182)	0.196

Table 2. Associations of carotid plaque characteristics from patients in top 20% of MetaGRS compared to the rest of the patients (80% of MetaGRS).

Values are displayed as n/total (%), unless otherwise specified. Values indicated as bold* are statistically significant. *OR*, odds ratio; *IPH*, intraplaque haemorrhage. Unadjusted OR indicates univariate analysis, adjusted OR indicates multivariable analysis. Multivariable analyses were corrected for age, sex, surgery year, cerebrovascular symptoms and additional confounders showing p<0.20 association with MetaGRS and the plaque characteristics of interest. Confounders included in various multivariable models can be found in Supplemental Table S2.

Categorical plaque characteristics	Unadjusted OR (95% CI)	Unadjusted p-value	Adjusted OR (95% CI)	Adjusted p-value
Moderate/heavy calcifications	0.917 (0.585-1.438)	0.706	0.777 (0.463-1.307)	0.342
Moderate/heavy collagen	1.168 (0.667-2.045)	0.586	1.294 (0.720-2.324)	0.389
Presence of lipid core >10%	1.785 (1.063-2.996)	**0.028***	1.885 (1.107-3.209)	**0.020***
Presence of IPH	1.560 (0.970-2.509)	0.066	1.652 (1.018-2.680)	**0.042***
Moderate/heavy smooth muscle cells	1.032 (0.624-1.706)	0.904	1.013 (0.598-1.714)	0.962
Moderate/heavy macrophages	1.446 (0.919-2.277)	0.111	1.468 (0.928-2.325)	0.101
Continuous plaque characteristics	**Unadjusted beta (95% CI)**	**Unadjusted p-value**	**Adjusted beta (95% CI)**	**Adjusted p-value**
Number of macrophages (median, IQR)	0.047 (-0.056-0.150)	0.373	0.041 (-0.060-0.143)	0.426
Number of smooth muscle cells (median, IQR)	-0.032 (-0.166-0.103)	0.646	-0.020 (-0.159-0.119)	0.782
Microvessels (median, IQR)	0.151 (-0.023-0.326)	0.089	0.146 (-0.027-0.318)	0.098

Table 3. Associations of MetaGRS (as continuous measure) and histological carotid plaque characteristics.

Values are displayed as n/total (%), unless otherwise specified. Values indicated as bold* are statistically significant. *OR*, odds ratio; *IPH*, intraplaque haemorrhage. Unadjusted OR indicates univariate analysis, adjusted OR indicates multivariable analysis. Multivariable analyses were corrected for age, sex, surgery year, cerebrovascular symptoms and additional confounders showing p<0.20 association with MetaGRS and the plaque characteristics of interest. Confounders included in various multivariable models can be found in Supplemental Table S2.


Patients that underwent CEA from March 2002-July 2016 (n=2,355)
Excluded for analysis
operated for restenosis (n=123)
lost to follow-up (n=188)
n=2,044
Excluded for analysis
No data on FHx (n=256)
Patients that fullfilled inclusion criteria with data on FHx (n=1,788)
Histological plaque characterization (n=1,551)
Genotyped (n=1,319)
Histological plaque characterization (n=1,301)



Positive family history				
Cumulative events	0	106	160	197
Total patients at risk	744	625	534	458
Negative family history				
Cumulative events	0	111	171	221
Total patients at risk	1,044	900	791	689



Top 20% of MetaGRS				
Cumulative events	0	42	62	78
Total patients at risk	264	219	192	165
Remaining 80% of MetaGRS				
Cumulative events	0	133	199	248
Total patients at risk	1,055	904	813	712



Top 20% of MetaGRS				
Cumulative events	0	42	62	78
Total patients at risk	264	219	192	165
Bottom 20% of MetaGRS				
Cumulative events	0	33	47	57
Total patients at risk	265	226	205	182


Secondary cardiovascular events during 3-year follow-up
Hazard ratio (95% CI)
3
2
1
0
Family history (FHx)
MetaGRS top 20% versus 80%
MetaGRS top 20% versus bottom 20%
MetaGRS (as continuous measure)
UV
MV
MV including MetaGRS
UV
MV
MV including FHx
UV
MV
MV including FHx
UV
MV