Mozambican Food Pyramid

Ernesto Francisco Maborre Fotinho[1,2,3]

[1]Lúrio University; [2]Lugenda Technical Institute; [3]Mozambican Nutritionists Association Member

Abstract

Introduction: In order to support nutritionists and other food and nutrition education actors in Mozambique in improving the approaches of intervention messages to fight for chronic malnutrition and other nutritional related diseases that plague the country, this work brings the adaptation of the American food pyramid published in 1993 to the local reality. **Methods**: The pyramid was built with the foods distributed in eight groups (Basic Foods, fruits, vegetables, legumes, milk, meats, fats and sugars) and in 5 levels. Each level was presented in minimum and medium portions to be consumed according to the established standard diets. The portions and the food equivalents tables were defined according to the caloric contribution of each food group using an automated spreadsheet of Microsoft Excel, version 19, and based on the principle of linear programming. The pyramid was based on two standard diets (1693 kcal and 2300 kcal) with four meals for both. **Results:** The percentage distribution of macronutrients in both diets is within the recommended range: Carbohydrates (45 to 65%), lipids (20 to 35%) and proteins (10 to 35%). Special attention was given to the milk group by calculating the bioavailable calcium values. **Discussion**: Factors such as food availability, dietary reference intake, and eating habits of the local population were elements of adaptation to the local context. **Conclusion**: Further studies are needed to validate and implement the instrument so that it becomes an effective and practical tool.

Keywords: Eating Habits; Food Pyramid; Mozambique

Key message:

- What is already known on this topic:

The tools that are currently used to promote healthy eating habits existing in parents present a gap regarding the portions of each food group that should be consumed, constituting a limitation for professionals in the area, who have been struggling to seek information on

graphic representations of foods from other countries that do not fit the local reality.

- What this study adds:

  This study brings an adaptation of a graphic representation of foods closer to the local reality, which includes foods that are part of the usual diet of the local population, their recommended portions and a list of substitute foods.

- How this study might affect research, practice or policy

  This study will contribute to the improvement of food and nutrition education messages and will serve as basic elements in the design of programs, strategies and intervention policies to combat chronic malnutrition that affects the country.

Introduction:

The chronic malnutrition is still a serious public health problem in Mozambique. According to the Household Budget Survey, the prevalence of disease in the country is 38%. [(1)]

The FAO held an international conference in Rome, in 1992 aiming to identify the strategies and actions to improve food consumption and the nutritional well-being of the population in order to fight for the diseases in the nutrition field. According to this event, the elaboration of food guides for different age groups should be encouraged and, to achieve this objective, each country should plan actions according to its culture and food related health problems. [(2)]

Food guides are instruments developed by governments or health institutions to guide the population on healthy eating practices. They are based on scientific evidence and adapted to the cultural and nutritional characteristics of each country or region. The main objective of food guides is to promote health and prevent diseases through recommendations on food choice and consumption. [(3)]

The Food Pyramid is a graphical representation of food guides, a recognizable nutritional tool introduced in 1992. It is shaped like a pyramid to suggest that a person consumes more food from the bottom of the pyramid and less food from the top. [(4)]

In Mozambique, the graphic representation used for food education is the 'Poster our food' drawn by MISAU [(5)] which consists of four food groups (Basic Foods, To Protect, To Grow and Concentrated Energy). This work brings a powerful proposal for adapting the food pyramid designed in the United States, in 1992 to the reality of the eating habits of Mozambicans. The Adapted Food Pyramid was built with foods distributed in eight groups (cereals, fruits, vegetables,

legumes, milk, meat, fats and sugars) and based on the tables of Mozambican foods compositions, minimum and average caloric consumption of the local population and their eating habits aiming to help nutritionists and other actors of food and nutrition education in Mozambique with improvement approaches and contributing to the reduction of food and nutrition education, chronic malnutrition and other nutritional related diseases that plague the country.

Methods

After an exhaustive literature review on different graphic representations of foods [(6)] and consulting different professionals in the area, the Food pyramid of foods proposed in the United States [(7)] was chosen. From this, a new Food Pyramid was built with a description of the groups and minimum and medium portions.

The following stages for the development of the proposal were:

1. Literature review on the different graphic representations of food and choice of elements to adapt and inspire: The review aimed to understand mainly the historical and methodological aspects for the graphic representations designing, experienced specialists in the different areas were also consulted;
2. The identification of Estimates of Minimum and Average Energy Needs of the Population: According to FAO, the minimum energy needs of Mozambicans is 1693 kcal. However, because of not finding the specific average needs for the local population, there was considered the general recommendation of 2,300 kcal with a variation of ± 20%. [(8-9)] In this study, the minimum energy requirements was applied to sedentary children and adolescents, while average energy requirements applied to physically active adolescents and sedentary adults. For pregnant women and physically active adults, they should follow specific recommendations.
3. Definition of food groups: The food pyramid was divided into 4 levels, as follows:

   - 1st level: Basic Foods (Derived Cereals and Tubers);
   - 2nd Level: Fruits and Vegetables;
   - 3rd Level: Meat, Milk and pulses;
   - 4th Level: Fats and sugars.

   Note that the name "Basic Foods" to indicate cereals and derivatives was inspired by the MISAU poster. [(5)]

4. Definition of portions for each food group: To define the portions, an automated spreadsheet of Microsoft Excel, version 19 was used, which integrates the principles of linear programming analysis of food composition. [10]
5. Designing of food equivalents table: To enable diversification options, a food equivalents table for fixed energy portions was prepared with the help of the spreadsheet and based on the Mozambican composition table. [11] The Shapiro-Wilk normality test was used to validate the means, assuming the P value greater than or equal to 5% and the standard deviation as a measure of dispersion. Statistical analyses were performed using SPSS, version 27.
6. The standard diet designing: For the validation of the proposal, a standard diet was designed for minimum and average energy value, distributed in four meals (Breakfast, Lunch, Snack and Dinner).

Results

To check the adequacy of the diet in relation to the recommendation of macronutrient intake, the percentage distribution of macronutrients was calculated for each diet, and for the diet of 1693 kcal, 19% of proteins (10 to 35%), 26% of lipids (20 to 35%) and 55% of carbohydrates (45 to 65%) were obtained. For the 2300 kcal diet, 19% of proteins (10 to 35%), 24% of lipids (20 to 35%), and 57% of carbohydrates (45 to 65%) were obtained, all values are within the recommended range. (12)

Table 1: Percentage distribution of macronutrients in diets

Diet (Kcal)	Carbohydrates (%)	Lipids (%)	Proteins (%)
1693	55	26	19
2300	57	24	19

Source: Automated spreadsheet of Microsoft Excel, version 19.

Tables 1 and 2 show a description of the minimum and average diets distributed in four meals. Both minimum and medium diet were composed of foods that are part of the eating habits of the local population, described in weight, household measurements, corresponding portion and the respective food group.

Table 2: 1693 kcal diet

FOOD	WEIGHT (g)	HOMEMADE MEASURE	PORTION	GROUP
Breakfast				
Whole milk powder	51	3 Tbsp	3	Milk and dairy products
Brown sugar	33	1 Tbsp	1/2.	Sugars
Coleslaw	249	18 Tbsp	1	Vegetables
Canned sardines	9	1 tsp	1/2.	Meats and eggs
Soybean oil	3	1 Teaspoon	1/2.	Oil and fats
Bread	44	1 Ordinary Bread	1	Basic food
Orange	134	1 Orange the size of a tennis ball	1	Fruits
Lunch				
White rice	64	2 Tbsp	2	Basic food
Fish	30	Hand hand size	1	Meats and eggs
Butter beans	29	1/2 ladle	1	Legumes
Raw eggplant	287	8 Tbsp	1.5	Vegetables
Sunflower oil	6	2 tsp	1	Oil and fats
Banana	65	1 Unit	1	Fruits
Afternoon snack				
Cookie	25	3 Units	1	Basic food
Maheu	46	1 small disposable cup	1/2.	Sugars
Dinner				
Corn Flour Cup	32	1 Ball*	1	Basic food
Beef	17	1/2 handle	1	Meats and eggs
Cabbage	182	1 cup of lunch	1.5	Vegetables
Sunflower oil	6	1 Teaspoon	1	Oil and fats
Pineapple	115	1 Slice	1	Fruits

Total Energy = 1659 kcal. Data obtained from Automated spreadsheet of Microsoft Excel, version 19.* Shell-sized ball, commonly designated locally.

The minimum diet showed the following percentage distribution of energy in the four meals: 33% for breakfast, 36% for lunch, 7% for afternoon snack and 23% for dinner.

Table 3: 2300 kcal diet

FOOD	WEIGHT (g)	HOMEMADE MEASURE	PORTION	GROUP
Breakfast				
Whole milk powder	51	3 Tbsp	3	Milk and dairy products
Brown sugar	33	1 Tbsp	1/2.	Sugars
Coleslaw	249	18 Tbsp	1	Vegetables
canned sardines	9	1 tsp	0.5	Meats and eggs
Soybean oil	3	1 Teaspoon	0.5	Oil and fats
Bread	66	1 Ordinary Bread	1.5	Basic food
Orange	201	2 Orange the size of a tennis ball	1.5	Fruits
Lunch				
White rice	80	3 Tbsp	2.5	Basic food
Fish	60	2 Hand handles size	2	Meats and eggs
Butter beans	58	1/2 Ladle	2	Legumes
Raw eggplant	382	11 Tbsp	2	Vegetables
Sunflower oil	9	2 tsp	1.5	Oil and fats
Banana	130	2 Units	2	Fruits
Afternoon snack				
Cookie	25	3 Units	1	Basic food
Maheu	46	1 small disposable cup	0.5	Sugars
Dinner				
Corn flour xima	80	2 Balls*	2.5	Basic food
Beef	34	1 put	2	Meats and eggs
Cabbage	242	1 cup of lunch	2	Vegetables
Sunflower oil	9	2 Teaspoons	1.5	Oil and fats
Pineapple	230	2 Slices	2	Fruits

Total Energy = 2209 kcal. Data obtained from Automated spreadsheet of Microsoft Excel, version 19. * Shell-sized ball, commonly designated locally.

The average diet showed the following percentage distribution of energy in the four meals: 29% for breakfast, 39% for lunch, 6% for afternoon snack and 31% for dinner.

The foods that make up the food pyramid (Figure 1) were grouped into four levels described in the methods and the number of portions for each of them was calculated, resulting in the following distribution:

First Level: Basic foods, source of compound carbohydrates, contribute with the largest source of calories in the diet, they include: cereals, tubers, roots and their derivatives (5 to 7.5 servings);

Second Level: Fruit Group and Vegetable Group, sources of vitamins and minerals (4 to 5 and 4 to 5.5 servings, respectively);

Third Level: Meat and Egg Group; milk and cheese and legume group, source of protein and calcium. The Meat and egg group include seafood and poultry typical of the region (2.5 to 4.5 servings). The milk and cheese group (3 servings). Legume Group includes oilseed legumes such as peanuts and soybeans and non-oilseeds such as beans (1 to 2 servings);

Fourth Level: Oils and Fats Group, a source of lipids, includes butter, margarine and olive oil (2.5 to 3.5 servings). Sugar Group, a source of simple carbohydrates, includes sugary products (2 servings)

Figure 1: Illustration of the food pyramid drawn



Figure legend

Food pyramid drawn, assembled from photos of local foods, taken from the following sources: PRN[5]; Dressup[13]; Ifrut[14]; Hortfruti[15]; Photography[16]; Dreamstime[17]; Organic[18], Cdifoodservice[19], Istockphoto[20], CozinhaBruta[21], Visãoonoticias[22], Banca13[23], Groupdream[24], CasaBhay[25], Secosdaaldeia[26], Amazon[27], Smilephotoap[28], Ramalho[29], Garden, Herbs[30], Orcapescados[31], Carolina[32], Cienciaviva[33], Sonho[34], Maré[35], Bazara[36], Liudmila[37], Volkov[38], Organic[39], CasaBhay[40], Redemix[41].

Discussion

This study aimed to design a food pyramid for Mozambique adapted to the local context, based on the old pyramid in the United States, published in 1993 by the Department of Agriculture [(7)], as a tool considered in this study as being the one that comes close to the local reality.

The study conducted by Fernandes et al. [(42)] aimed to design a food pyramid that represented all the countries of Sub-Saharan Africa. However, due to the diversity of cultures and the lack of information on defined portions, its application in the local context as an integral part of it may be a challenge. Because of that, and with little information in the literature on the specific food pyramid for Mozambique, this study aimed to close the gap by bringing a proposal for this tool. At the local level, there is a poster designed by the Ministry of Health [(5)], but the similarity of the graphic representation proposed by Fernandes [(42)] does not provide information about the portions of food, thus subjectivizing the messages of food education. The size of the portions defined in this study took into account the eating habits described by Machamba [(43)], food availability and the diversity of crops in which Mozambique is rich [(44)].

The adapted pyramid was designed with diets of minimum and average caloric needs while the original one was designed with three values (minimum energy needs, 1600 kcal. average, 2200 kcal. and maximum, 2800 kcal). The group of cereals and derivatives constitutes the basis of the diet of Mozambicans, which, according to Machamba [(43)], with an average consumption of 725 g/day, followed by tubers, with an intake of 331, in this study, the consumption of cereals in portions is about 240 g for cereals and 1088 g for tubers, because in the usual quantities the contribution of carbohydrates exceeds the recommended standards. For the fruit and vegetable group, we tried to approximate the portions defined in this study (4 to 5 portions) with those recommended by the WHO [(45)] (consumption greater than or equal to 400 g/day). The Meat group is the least consumed group in Mozambique, once, according to Machamba [(43)], the average daily consumption is only 11 g, a fact that may be contributing to the levels of chronic malnutrition that plagues the country, especially in children under 5 years, as revealed by INE data [(46)]. To fill this need, this study defined the consumption of 4 to 4.5 daily servings of this food group. The group of milk and dairy products deserved special attention because it is an important source of calcium and, according to the WHO [(18)], is associated with the prevention of bone diseases and cancer. With the consumption of the portions recommended in the pyramid of this study (3 daily servings), it is possible to supply 453 mg to 528 mg of this mineral, which corresponds to 50% of the

Recommended Dietary Allowance [19]. The legume group in the United States pyramid was included in the meat group, but given the importance of the group in the local diet, which serves as an alternative source of protein, especially in populations living in rural areas of Mozambique, due to its low production cost and affordability [20], it was placed separately as a separate group, with a recommendation of between 1 and 2 daily portions. The group of sugars, oils and fats constituted the group at the top of the pyramid that should be consumed with caution. For the Sugars group, consumption is limited to less than 10% of total calories because its excessive consumption is associated with chronic non-communicable diseases. [18] In this study, the caloric contribution of this group is approximately 1%. Similarly to the group of Fats and Oils, consumption is limited to between 15 and 30% of the total value of energy [18], in this study, the diets of this group contribute with 19% of the total calories of the diets.

Conclusion

The food pyramid developed is presented as a guidance tool for nutritionists and other actors in food and nutrition education in Mozambique. The instrument was adapted considering factors such as availability, reference dietary intake, and eating habits of the local population. Attention was paid to energy balance when developing standard diets with minimum calories consumed by the general population and those recommended on average. The portion sizes and the list of food equivalents are adapted to the population's eating habits and frequency of food consumption. Special attention was given to the milk group, the portions and their size were defined to supply 50% of the dietary reference intake of calcium. Further studies are needed to validate and implement the instrument so that it becomes an effective and practical tool.

References

1. National Institute of Statistics. Household Budget Survey-IOF 2019/20 Nutritional status of children under 5 years and household perceptions of food security Supplement Final report October 2021.
2. WHO. Forty-Sixth World Health Assembly Provisional Agenda Item 18 International Conference on Nutrition Report by The Director-General. Rome; 1993.
3. Ministry of Health. Health Care Secretariat. Department of Primary Care. Food Guide for the Brazilian Population. Http://Bvsms.Saude.Gov.Br/Bvs/Publicacoes/Guia_Alimentar_Populacao_Brasileira_2ed.Pdf. Brazil; 2014.
4. Marcus Jb. Food Science Basics: Healthy Cooking and Baking Demystified. In: Culinary Nutrition. Elsevier; 2013. p. 51–97.
5. MISAU. Manual of Nutritional Treatment and Rehabilitation Volume I: 0 to 14 years old. 2nd Edition. Republic of Mozambique: Ministry of Health, Department of Nutrition; 2018.
6. FAO. Www.Fao.Org. 2024 [Cited 2024 May 31]. Food-Based Dietary Guidelines. Available From: Https://Www.Fao.Org/Nutrition/Education/Food-Dietary-Guidelines/En
7. Susan O. Welsh Carole Davis Anne Shaw. USA's Food: Guide Background and Development. Us; 1993.
8. FAO. Www.Fao.Org. 2024 [Cited 2024 May 29]. Suite Of Food Security Indicators. Available From: Https://Www.Fao.Org/Faostat/En/#Data/Fs
9. Press F. Recommended Dietary Allowances (10th Edition). J Am Diet Assoc. 1985; 85(1644-1645.).
10. Ferguson El, Darmon N, Briend A. Food-Based Dietary Guidelines Can Be Developed and Tested Using Linear Programming Analysis. Journal Of Nutrition. 2004; 134(4):951–7.
11. Korkalo L, Hauta-Alus H, Mutanen M. Food Composition Tables for Mozambique. 2011.
12. Institute Of Medicine. Dietary Reference Intakes for Energy, Carbohydrate, Fiber, Fat, Fatty Acids, Cholesterol, Protein, And Amino Acids (Macronutrients) [Internet]. Dietary Reference Intakes for Energy, Carbohydrate, Fiber, Fat, Fatty Acids, Cholesterol, Protein, And Amino Acids (Macronutrients). Washington: National Academies Press; 2005 [cited 2024 Jun 24]. 1–1331 P. Available From: Https://Doi.Org/10.17226/10490.
13. Get dressed. Learn How to Find Out If the French Bread from The Bakery Near Your Home Is Vegan [Internet]. 2007 [cited 2024 Jul 1]. Available From: Https://Www.Vista-Se.Com.Br/Aprenda-A-Descobrir-Se-O-Pao-Frances-Da-Padaria-Perto-Da-Sua-Casa-E-Vegano/
14. Ifrutus. Washed Potato [Internet]. [Cited 2024 Jul 1]. Available From: Https://Www.Ifrutus.Com.Br/Produto/Batata-Lavada-500g-70629
15. Produce. Organic Green Cabbage [Internet]. [Cited 2024 Jul 1]. Available From:

Https://Hortifruti.Com.Br/Repolho-Verde-Organico.Html
16. Jobz Photography. Adobe Stock. [Cited 2024 Jul 1]. Kale 1. Available From: Https://Stock.Adobe.Com/Pt/Search?K=Couve&Asset_Id=51549822
17. Dreamstime. Dreamstime. 2024 [cited 2024 jul 1]. Image of papaya fruits. Available From: Https://Pt.Dreamstime.Com/Fotografia-De-Stock-Imagem-De-Frutas-Da-Papaia-Image21547852
18. Organic Hortifruti. Hortifrutiorganico.Com.Br. 2024 [cited 2024 Jul 7]. Organic Silver Banana. Available From: Https://Www.Hortifrutiorganico.Com.Br/Inicio/44-Banana-Organica-Prata-1-Kg.Html
19. Sp.Cdifoodservice. Com.Br. Https://Sp.Cdifoodservice.Com.Br. 2024. Sunflower Oil .
20. Istockphoto. Istockphoto.Com. 2024. Margarine Tub Vector.
21. Raw cuisine. Https://Cozinhabruta.Blogfolha.Uol.Com.Br. 2024. Folha de S.Paulo.
22. Vision News. Visaonoticias.Com. 2024. Visãonews.
23. Banca13. Https://Www.Banca13.Com.Br. 2024. Pure Honey.
24. Groupdream. 2024 [cited 2024 Jul 14]. Feijão Holoco. Available From: Https://Groupdream.Co.Mz
25. Casa Bhay. Krolyc.Co.Mz. 2024. Nhemba Beans.
26. Secosdaaldeia. Secosdaaldeia-Loja.Pt. 2024. Butter Beans.
27. Amazon. Https://Www.Amazon.Com.Br. 2024 [Cited 2024 Jul 12]. Minas Cheese Half Cured. Available From: Https://Www.Amazon.Com.Br/Queijo-Minas-Meia-Cura-Metade/Dp/B0clqg8kkh
28. Smilephotoap. Https://Br.Freepik.Com. 2024 [Cited 2024 Jul 12]. Natural Whole Milk. Available From: Https://Br.Freepik.Com/Fotos-Premium/Leite-Integral-Natural-Em-Uma-Jarra-E-Um-Copo-Isolado-Em-Um-Fundo-Branco_16487094.Htm
29. Assis Ramalho. Assisramalho.Com.Br. 2024 [cited 2024 jul 12]. Fresh Fish. Available From: Https://Www.Assisramalho.Com.Br/2014/04/Dra-Cintia-Campos-Aproveita-Tradicao-De.Html
30. Herb Garden. Jardimdaservas.Com.Br. 2024. Pea Chickpeas.
31. Budgeted. Https://Orcapescados.Com.Br. 2024. Clean Octopus.
32. Carolina. Baby food. 2024. Egg.
33. Cienciaviva. Https://Www.Cienciaviva.Pt. 2024. Lula.
34. Secrets of the dream. Segredosdosonho.Com. [cited 2024 Jul 11]. Dream of chicken. Available From: Https://Www.Segredosdosonho.Com.Br/Sonhar-Com-Frango/
35. Casa Maré. House sea fish. 2024 [Cited 2024 Jul 11]. Pink Pistol Shrimp. Available From: Https://Www.Casamarepescados.Com.Br/Produto/Camarao-Rosa-Pistola-810-Inteiro?Variant_Id=201
36. Bazaar. Https://Bazara.Co.Mz. 2022. Goat's meat.
37. Liudmila Bf. Shutterstock.Com. 2024. Exotic Fruit of Mozambique.
38. Valentyn Volkov. Depositphotos.Com. 2024. Orange fruits.
39. Organic Hortifruti. Hortifrutiorganico.Com.Br. 2024 [cited 2024 Jul 7]. Organic Silver

Banana. Available From: Https://Www.Hortifrutiorganico.Com.Br/Inicio/44-Banana-Organica-Prata-1-Kg.Html
40. Bhay House. Krolyc.Co.Mz. 2024 [cited 2024 Jul 8]. Fruit Pineapple. Available From: Https://Krolyc.Co.Mz/Loja/Comida-E-Mercearia/Fruta/Frut-Ananas-Kg/
41. Redemix. Palmer Mango [Internet]. 2024 [cited 2024 jul 8]. Available From: Https://Www.Redemix.Com.Br/3442manga-Palmer-1-Unidade-400g/P
42. Fernandes T, Garrine C, Ferrão J, Bell V, Varzakas T. Mushroom Nutrition As Preventative Healthcare In Sub-Saharan Africa. Vol. 11, Applied Sciences (Switzerland). Mdpi Ag; 2021.
43. Machamba A. Development and pre-test of a food frequency questionnaire in the city of Nampula, Mozambique. 2014.
44. Ciríaco Mif. Mozambique: cultural and linguistic diversity. Postgraduate Notebooks in letters 2017; 17(1).
45. World Health Organization. Diet, Nutrition, And the Prevention of Chronic Diseases: Report of A Joint Who/Fao Expert Consultation. World Health Organization; 2003. 149 p.
46. Ine. Household Budget Survey-IOF 2019/20 Nutritional status of children under 5 years of age and household perceptions of food security Supplement Final report October 2021. 2021.
47. World Health Organization. Diet, Nutrition, And the Prevention of Chronic Diseases: Report of A Joint Who/Fao Expert Consultation. World Health Organization; 2003. 149 p.
48. Ross AC, Institute of Medicine (U.S.). Committee To Review Dietary Reference Intakes for Vitamin D And Calcium. Dri, Dietary Reference Intakes: Calcium, Vitamin D. National Academies Press; 2011. 1115 p.
49. Charrua Ab, Havik Pj, Bandeira S, Catarino L, Ribeiro-Barros A, Cabral P, Et Al. Food Security and Nutrition In Mozambique: Comparative Study With Bean Species Commercialized In Informal Markets. Sustainability (Switzerland). 2021 Aug 2; 13(16).

Competing Interest

None to declare

Funding

The study was unfunded

Appendix

Appendix 1

Cereals and derivatives, equivalent tubers (113 kcal)	Serving Size (g)
Biscuit, plain, commercial	25
Biscuit, with cream filling, commercial	24
Dried noodles	31
Raw oats	28
White rice, polished, uncooked	32
Whole grain sorghum, raw	32
Corn flour	32
White wheat flour	31
Sorghumi Flour*	32
Dried cassava	35
Mexoeira Flour	34
Bread	44
Cassava flour	32
Mean (Standard Deviation)	**32 (±5)**
Skinless yams, raw	132
Peeled potatoes, raw	141
Orange-fleshed sweet potato, raw	145
Average	*

* Deviation from Normality

Appendix 2

Fruits and equivalents (63 kcal)	Serving Size (g)	Ener. (Kcal)
Medium apple with peel	105	63
Pear with peel	103	63
Peeled pineapple	115	63
Peeled guava	115	63
Peeled tangerine	113	63
Mean (Standard Deviation)	**110 (±6)**	**63 (±0)**
Peeled lemon	154	63
Orange pulp melon	162	63
Fresh cashew	140	63
Mean (Standard Deviation)	**152 (±11)**	**63 (±0)**
Peeled orange	134	63
Peeled grapefruit	180	63
Peeled ripe mango	90	63
Peeled banana	65	63
Peeled purple passion fruit	72	63
Peeled watermelon	210	63
Mean (Standard Deviation)	*	**63 (±0)**

* Deviation from Normality

Appendix 3

Vegetables and equivalents (68 kcal)	Serving Size (g)	Ener. (Kcal)
Raw sweet potato leaves	166	68
Green, raw, medium leaves	146	68
Carrot, peeled, raw	176	68
Raw pumpkin leaves	145	68
Boiled amaranth leaves	158	68
Raw cowpea leaves	163	68
Mean (Standard Deviation)	**159 (±12)**	**68 (±0)**
Raw cabbage	249	68
Raw pumpkin	250	68
Raw amaranth leaves	273	68
Mean (Standard Deviation)	**257 (±14)**	**68 (±0)**
Raw kale	121	68
Okra, green beans, raw	219	68
Cooked cowpea leaves	200	68
Raw eggplant	191	68
Raw cassava leaves	65	68
Mean (Standard Deviation)	*	**68 (±0)**

* Deviation from Normality

Appendix 4

Milk and equivalent dairy products (85Kcal)	Serving Size (g)	Lime (mg)
Fresh cow's milk, 2% fat	170	234
Fresh cow's milk, whole	137	164
Goat milk	100	160
Fruit yogurt, low-fat, sweetened with sugar	100	145
Mean (Standard Deviation)	*	176 **(±40)**
Cheese, cheddar	22	171
Feta	26	100
Cheese, mozzarella	29	146
Gouda cheese	23	185
Whole milk powder	17	155
Mean (Standard Deviation)	*	151 **(±32)**

*Deviation from Normality

Appendix 5

Fats, Oils and equivalents (51 kcal)	Serving Size (g)
butterpaste, Clover Butro	8
Salted butter	7
Margarine, Biba, Amanda	7
Margarine, Flora	9
Margarine, Branch, Brick	7
mayonnaise	10
oil, coconut	6
olive oil, olive	6
Palm Oil	6
oil, soybean	6
sunflower oil	6
Mean (Standard Deviation)	**7**

	(±2)

Appendix 6

Sugars and Sweets (17 kcal)	Serving Size (g)
non-alcoholic cereal drink (Maheu)	92
Sugar Cane, Juice	23
Honey	5
Brown sugar	66
Average	*

*Deviation from Normality